Tazewell County Highway Department

AUTHORIZATION TO BID FORM

Addenda will be published to our Bid Letting page in the same manner as the plans and specifications. It is the sole responsibility of the plan holders to periodically check the website for plan addenda.

ALL BIDDERS PLANNING TO PLACE A BID MUST FILL OUT THIS FORM TO BE AUTHORIZED TO BID.

- This form must be completed, signed and either faxed to (309) 925-5533 or emailed to jsciortino@tazewell-il.gov.
- Failure to submit this completed form will result in the bid not being accepted.
- Contractors may verify we have received their Authorization to Bid form by checking the **Plan Holders List** found under the corresponding letting date.
- If an email address is provided, a Notice of Addenda will be sent when updates are available.
- Bid results are typically posted by noon on the day of the letting and are preliminary until approved by the County Board on the last Wednesday of the month.

Company Name:	
Address:	
///////////////////////////////////////	
Phone:	
Fax:	
Email:	
Bid Letting Date:	

Projects Intending to Bid on:

Section Number:	Description:

Tazewell County Highway Department 21308 Illinois Route 9 Tremont, IL 61568 p: (309) 925-5532 • f: (309) 925-5533 • jsciortino@tazewell-il.gov



COVER	SHEET			
Proposal Submitted By:				
Contractor's Name				
Contractor's Address	City			State Zip Code
STATE OF ILLINOIS				
Local Public Agency		County		Section Number
Tazewell County		Tazewell	2	23-00018-06-RS
Route(s) (Street/Road Name)			Type of Fund	ds
Washington Rd. (CH 3)			MFT & RB	51
Proposal Only Roposal and Plans Proposal only, plans	are separa	te		
Submitted/Approved For Local Public Agency: For a County and Road District Project		For a	Aunicipal Dro	iest
For a County and Road District Project		For a l	Municipal Pro	oject
Submitted/Approved		Submitte	d/Approved/P	assed
Highway Commissioner Signature & Date	Signatu	re & Date		
	Official	Title		
Submitted/Approved				
County Engineer/Superintendent of Highways Signature & Date				
Dan Parr Date: 2023.02.24 08:59:33 -06'00'		Departme	ent of Transp	ortation
		Released for b	oid based on l	imited review
	Regiona	al Engineer Signa]
	Ken	sil A. Gar	nett Garne	ly signed by Kensil A. tt 2023.03.24 16:26:37 -05'00'

Note: All proposal documents, including Proposal Guaranty Checks or Proposal Bid Bonds, should be stapled together to prevent loss when bids are processed.

Loc	cal Public Agency	County	Section Number	Route(s) (Stre	et/Road Name)	
Та	zewell County	Tazewell	23-00018-06-RS	Washingtor	n Rd. (CH 3)	
			O BIDDERS			
Sor	aled proposals for the project describ			County Engine	eer	
000	aled proposals for the project describ			Name of Off	ice	
21	308 IL Route 9, Tremont, IL 6	1568	un	_{til} 1:30 PM	on 04/13/23	
		Address		Time	Date	
Sea	aled proposals will be opened and re	ad publicly at the office of the	e Tazewell County Engl	Ineer ame of Office		
21	308 IL Route 9, Tremont, IL 6 ⁻	1568		ane of Office	on 04/13/23	
	, <u></u>	Address		Time	OII Date	
		DESCRIPTIO	ON OF WORK			
Loc	cation				Project Length	
Wa	ashington Rd. (CH 3) - City of	Washington south to US	S 150		5.285 Miles	
Pro	pposed Improvement					
Hc	ot-Mix Asphalt Milling and Res	urfacing.				
1. F	Plans and proposal forms will be ava	ilable in the office of				
	e Tazewell County Engineer					
	308 IL Route 9					
L	emont, IL 61568					
2.	 Prequalification If checked, the 2 apparent as read 	low hiddoro must filo within 2	1 hours ofter the latting on "/		aility" (Form PC 57) in	
	triplicate, showing all uncompleted and private work. One original shall	contracts awarded to them ar	nd all low bids pending awar	d for Federal, Sta	ite, County, Municipal	
3.	The Awarding Authority reserves th Provision for Bidding Requirements			osals as provideo	l in BLRS Special	
4.	The following BLR Forms shall be r a. Local Public Agency Formal Co b. Schedule of Prices (BLR 1220	ontract Proposal (BLR 12200				
	c. Proposal Bid Bond (BLR 1223)d. Apprenticeship or Training Proe. Affidavit of Illinois Business Official	gram Certification (BLR 1232)	
5.	5. The quantities appearing in the bid schedule are approximate and are prepared for the comparison of bids. Payment to the Contractor will be made only for the actual quantities of work performed and accepted or materials furnished according to the contract. The scheduled quantities of work to be done and materials to be furnished may be increased, decreased or omitted as hereinafter provided.					
6.	6. Submission of a bid shall be conclusive assurance and warranty the bidder has examined the plans and understands all requirements for the performance of work. The bidder will be responsible for all errors in the proposal resulting from failure or neglect to conduct an in depth examination. The Awarding Authority will, in no case, be responsible for any costs, expenses, losses or changes in anticipated profits resulting from such failure or neglect of the bidder.					
7.	The bidder shall take no advantage	of any error or omission in th	ne proposal and advertised c	ontract.		
8.	If a special envelope is supplied by Awarding Agency and the blank spa					

- Awarding Agency and the blank spaces on the envelope shall be filled in correctly to clearly indicate its contents. When an envelope other than the special one furnished by the Awarding Authority is used, it shall be marked to clearly indicate its contents. When an envelope other than the special one furnished by the Awarding Authority is used, it shall be marked to clearly indicate its contents. When sent by mail, the sealed proposal shall be addressed to the Awarding Authority at the address and in care of the official in whose office the bids are to be received. All proposals shall be filed prior to the time and at the place specified in the Notice to Bidders. Proposals received after the time specified will be returned to the bidder unopened.
- 9. Permission will be given to a bidder to withdraw a proposal if the bidder makes the request in writing or in person before the time for opening proposals.

Loc	al Public Agency	County	Section Number	Route(s) (Street/Road Name)
Ta	zewell County	Tazewell	23-00018-06-RS	Washington Rd. (CH 3)
			PROPOSAL	
1.	Proposal of			
			Contractor's Name	
		Со	ontractor's Address	
2.	The plans for the proposed v	vork are those prepared by the	e Tazewell County Highway	Department
i	and approved by the Departr	ment of Transportation on Ma	ır 24, 2023	
3.		Bridge Construction" and the	y the Department of Transportation " Supplemental Specifications and	on and designated as "Standard d Recurring Special Provisions" thereto,
4.		accept, as part of the contract s" contained in this proposal.	, the applicable Special Provisions	s indicated on the "Check Sheet for
	The undersigned agrees to is granted in accordance wit	complete the work within $\underline{30}$ th the specifications.	working days or by	unless additional time
		time of execution of the cont		eposit a contract bond for the full amount of
	the award. When a contract and the undersigned fails to forfeited to the Awarding Au	execute a contract and contra	oosal guaranty check will be held i act bond as required, it is hereby a	n lieu thereof. If this proposal is accepted agreed that the Bid Bond of check shall be
	the unit price multiplied by the	he quantity, the unit price shal	I govern. If a unit price is omitted,	e is a discrepancy between the products of the total price will be divided by the nit price nor a total price is shown.
8.	The undersigned submits he	erewith the schedule of prices	on BLR 12201 covering the work	to be performed under this contract.
9.				e combinations on BLR 12201, the work I specified in the Schedule for Multiple Bids
10.	A proposal guaranty in the	proper amount, as specified ir	BLRS Special Provision for Biddi	ing Requirements and Conditions for
		epartment form BLR 12230 or	a proposal guaranty check, comp	ranty. Accompanying this proposal is either lying with the specifications, made payable
			Treasurer of Tazewell County	
	The amount of the check is			().
		Attach Cashier's	Check or Certified Check Here	
	sum of the proposal guarar		for each individual bid proposal. If	als, the amount must be equal to the f the proposal guaranty check is
	The proposal guaranty che	ck will be found in the bid pro	posal for: Section Number	

Local Public Agency	County	Section Number	Route(s) (Street/Road Name)
Tazewell County	Tazewell	23-00018-06-RS	Washington Rd. (CH 3)

CONTRACTOR CERTIFICATIONS

The certifications hereinafter made by the bidder are each a material representation of fact upon which reliance is placed should the Department enter into the contract with the bidder.

- 1. **Debt Delinquency.** The bidder or contractor or subcontractor, respectively, certifies that it is not delinquent in the payment of any tax administered by the Department of Revenue unless the individual or other entity is contesting, in accordance with the procedure established by the appropriate Revenue Act, its liability for the tax or the amount of the tax. Making a false statement voids the contract and allows the Department to recover all amounts paid to the individual or entity under the contract in a civil action.
- 2. **Bid-Rigging or Bid Rotating**. The bidder or contractor or subcontractor, respectively, certifies that it is not barred from contracting with the Department by reason of a violation of either 720 ILCS 5/33E-3 or 720 ILCS 5/33E-4.

A violation of section 33E-3 would be represented by a conviction of the crime of bid-rigging which, in addition to Class 3 felony sentencing, provides that any person convicted of this offense, or any similar offense of any state or the United States which contains the same elements as this offense shall be barred for 5 years from the date of conviction from contracting with any unit of State or local government. No corporation shall be barred from contracting with any unit of State or local government as a result of a conviction under this Section of any employee or agent of such corporation if the employee so convicted is no longer employed by the corporation: (1) it has been finally adjudicated not guilty or (2) if it demonstrates to the governmental entity with which it seeks to contract that entity finds that the commission of the offense was neither authorized, requested, commanded, nor performed by a director, officer or a high managerial agent on behalf of the corporation.

A violation of Section 33E-4 would be represented by a conviction of the crime of bid-rotating which, in addition to Class 2 felony sentencing, provides that any person convicted of this offense or any similar offense of any state or the United States which contains the same elements as this offense shall be permanently barred from contracting with any unit of State of Local government. No corporation shall be barred from contracting with any unit of State or Local government as a result of a conviction under this Section of any employee or agent of such corporation if the employee so convicted is no longer employed by the corporation and: (1) it has been finally adjudicated not guilty or (2) if it demonstrates to the governmental entity with which it seeks to contract and that entity finds that the commission of the offense was neither authorized, requested, commanded, nor performed by a director, officer or a high managerial agent on behalf of the corporation.

- 3. **Bribery.** The bidder or contractor or subcontractor, respectively, certifies that, it has not been convicted of bribery or attempting to bribe an officer or employee of the State of Illinois or any unit of local government, nor has the firm made an admission of guilt of such conduct which is a matter or record, nor has an official, agent, or employee of the firm committed bribery or attempted bribery on behalf of the firm and pursuant to the direction or authorization of a responsible official of the firm.
- 4. **Interim Suspension or Suspension.** The bidder or contractor or subcontractor, respectively, certifies that it is not currently under a suspension as defined in Subpart I of Title 44 Subtitle A Chapter III Part 6 of the Illinois Administrative code. Furthermore, if suspended prior to completion of this work, the contract or contracts executed for the completion of this work may be canceled.

Local Public Agency	County	Section Number	Route(s) (Stree	t/Road Name)			
Tazewell County	Tazewell	23-00018-06-RS	Washington	Rd. (CH 3)			
	SIGN	ATURES					
(If an individual)		Bidder Signature & Date					
		Business Address					
	(Г	City	State	Zip Code			
	1	Firm Name					
(If a partnership)							
		Signature & Date					
	-	Title					
	l r	Business Address					
	([City	State	Zip Code			
Insert the Names and Addresses of all P	artners						
		Corporate Name					
(If a corporation)							
	L	Signature & Date					
		0					
	L	Title					
		Business Address					
	((City	State	Zip Code			
Incort	Names of Officers	President					
insert.							

Secretary

Attest:

Treasurer

Secretary





Contractor's Name

Contractor's Address	City		State	Zip Code	
Local Public Agency		County	Section N	lumber	
Tazewell County		Tazewell	23-000	8-06-RS	
Route(s) (Street/Road Name)					
Washington Rd. (CH 3)					

Schedule for Multiple Bids

Combination Letter	Section Included in Combinations	Total

Schedule for Single Bid

(For complete information covering these items, see plans and specifications.)

Item Number	Items	Unit	Quantity	Unit Price	Total
1	P BIT MATLS TACK CT	POUND	145841		
2	HMA SURF REM BUTT JT	SQ YD	1800		
3	TEMPORARY RAMP	SQ YD	140		
4	HMA BC IL-9.5FG N50	TON	6942		
5	P HMA SC IL-9.5 D N50	TON	8331		
6	MATL TRANSFER DEVICE	TON	8331		
7	INCIDENTAL HMA SURF	TON	353		
8	HMA SURF REM 1 1/2	SQ YD	98296		
9	AGGREGATE SHLDS B SPL	TON	1534		
10	SHORT TERM PAVT MKING	FOOT	19952		
11	SHRT TRM PAVT MK REM	SQ FT	1663		
12	RAISED REFL PAVT MKR	EACH	347		
13	RAISED REF PVT MK REM	EACH	347		
14	CL D PATCH T4 6	SQ YD	1182		
15	RR PROT LIABILITY INS	L SUM	1		
16	TRAF CONT & PROT SPL	L SUM	1		
17	MOBILIZATION	L SUM	1		
		·	Bi	dder's Total Proposal	

- 1. Each pay item should have a unit price and a total price.
- 2. If no total price is shown or if there is a discrepancy between the product of the unit price multiplied by the quantity, the unit price shall govern.

Local Public Agency	County	Section Number	Route(s) (Street/Road Name)
Tazewell County	Tazewell	23-00018-06-RS	Washington Rd. (CH 3)

3. If a unit price is omitted, the total price will be divided by the quantity in order to establish a unit price.

4. A bid may be declared unacceptable if neither a unit price or total price is shown.



Local Public Agency Proposal Bid Bond

Local Public Agency	County	Section Number
Tazewell County	Tazewell	23-00018-06-RS
WE.		as PRINCIPAL and

as SURETY, are held jointly,

severally and firmly bound unto the above Local Public Agency (hereafter referred to as "LPA") in the penal sum of 5% of the total bid price, or for the amount specified in the proposal documents in effect on the date of invitation for bids, whichever is the lesser sum. We bind ourselves, our heirs, executors, administrators, successors, and assigns, jointly pay to the LPA this sum under the conditions of this instrument.

WHEREAS THE CONDITION OF THE FOREGOING OBLIGATION IS SUCH that, the said PRINCIPAL is submitting a written proposal to the LPA acting through its awarding authority for the construction of the work designated as the above section.

THEREFORE if the proposal is accepted and a contract awarded to the PRINCIPAL by the LPA for the above designated section and the PRINCIPAL shall within fifteen (15) days after award enter into a formal contract, furnish surety guaranteeing the faithful performance of the work, and furnish evidence of the required insurance coverage, all as provided in the "Standard Specifications for Road and Bridge Construction" and applicable Supplemental Specifications, then this obligation shall become void; otherwise it shall remain in full force and effect.

IN THE EVENT the LPA determines the PRINCIPAL has failed to enter into a formal contract in compliance with any requirements set forth in the preceding paragraph, then the LPA acting through its awarding authority shall immediately be entitled to recover the full penal sum set out above, together with all court costs, all attorney fees, and any other expense of recovery.

IN TESTIMONY WHEREOF, the said PRINCIPAL and the said SURETY have caused this instrument to be signed by their respective officers this of

Day	Month and Year Principal
Company Name	Company Name
Signature & Date	Signature & Date
By:	By:
T-141 -	Title
Title	
	ontractors, the company names, and authorized signatures of each contractor must be
affixed.)	Surety
Name of Surety	Signature of Attorney-in-Fact Signature & Date
	Ву:
STATE OF IL	
COUNTY OF	
I	, a Notary Public in and for said county do hereby certify that
(Insert na	nes of individuals signing on behalf of PRINCIPAL & SURETY)
	e same persons whose names are subscribed to the foregoing instrument on behalf of
	e this day in person and acknowledged respectively, that they signed and delivered said
Given under my hand and notarial seal this	day of
	Day Month and Year
	Notary Public Signature & Date
(SEAL, if required by the	LPA)
	Date commission expires

Local Public Agency	County	Section Number
Tazewell County	Tazewell	23-00018-06-RS

ELECTRONIC BID BOND

Electronic bid bond is allowed (box must be checked by LPA if electronic bid bond is allowed)

The Principal may submit an electronic bid bond, in lieu of completing the above section of the Proposal Bid Bond Form. By providing an electronic bid bond ID code and signing below, the Principal is ensuring the identified electronic bid bond has been executed and the Principal and Surety are firmly bound unto the LPA under the conditions of the bid bond as shown above. (If PRINCIPAL is a joint venture of two or more contractors, an electronic bid bond ID code, company/Bidder name title and date must be affixed for each contractor in the venture.)

Electronic Bid Bond ID Code

Company/Bidder Name

Signature & Date

Title



Affidavit of Availability



For the Letting of

Bureau of Construction 2300 South Dirksen Parkway/Room 322 Springfield, IL 62764 Instructions: Complete this form by either typing or using black ink. "Authorization to Bid" will not be issued unless both sides of this form are completed in detail. Use additional forms as needed to list all work.

Part I. Work Under Contract

List below all work you have under contract as either a prime contractor or a subcontractor. It is required to include all pending low bids not yet awarded or rejected. In a joint venture, list only that portion of the work which is the responsibility of your company. The uncompleted dollar value is to be based upon the most recent engineer's or owners estimate, and must include work subcontracted to others. If no work is contracted, show NONE.

	1	2	3	4	Awards Pending	Accumulated Totals
Contract Number						
Contract With						
Estimated Completion Date						
Total Contract Price						
Uncompleted Dollar Value if Firm is the Prime Contractor						
Uncompleted Dollar Value if Firm is the Subcontractor						
Total Value of All Work						

Part II. Awards Pending and Uncompleted Work to be done with your own forces.

List below the uncompleted dollar value of work for each contract and awards pending to be completed with your own forces. All work subcontracted to others will be listed on the reverse of this form. In a joint venture, list only that portion of the work to be done by your company. If no work is contracted, show NONE.

1 2	,			
Earthwork				
Portland Cement Concrete Paving				
HMA Plant Mix				
HMA Paving				
Clean & Seal Cracks/Joints				
Aggregate Bases, Surfaces				
Highway, R.R., Waterway Struc.				
Drainage				
Electrical				
Cover and Seal Coats				
Concrete Construction				
Landscaping				
Fencing				
Guardrail				
Painting				
Signing				
Cold Milling, Planning, Rotomilling				
Demolition				
Pavement Markings (Paint)				
Other Construction (List)				
Totals				

Disclosure of this information is REQUIRED to accomplish the statutory purpose as outlined in the "Illinois Procurement Code." Failure to comply will result in non-issuance of an "Authorization To Bid." This form has been approved by the State Forms Management Center.

Part III. Work Subcontracted to Others.

For each contract described in Part I, list all the work you have subcontracted to others.

	1	2	3	4	Awards Pending
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					

Total Uncompleted

Notary

I, being duly sworn, do hereby declare this affidavit is a true and correct statement relating to ALL uncompleted contracts of the undersigned for Federal, State, County, City and private work, including ALL subcontract work, ALL pending low bids not yet awarded or rejected and ALL estimated completion dates.

Officer or Director	
Title	
Signature	Date
Company	
Address	
City	State Zip Code

Subscribed and sworn to before me this day of ,
(Signature of Notary Public) My commission expires
(Notary Seal)

Add pages for additional contracts



Apprenticeship and Training Program Certification

Local Public Agency	County	Street Name/Road Name	Section Number
Tazewell County	Tazewell	Washington Rd. (CH 3)	23-00018-06-RS

All contractors are required to complete the following certification

For this contract proposal or for all bidding groups in this deliver and install proposal.

For the following deliver and install bidding groups in this material proposal.

Illinois Department of Transportation policy, adopted in accordance with the provisions of the Illinois Highway Code, requires this contract to be awarded to the lowest responsive and responsible bidder. The award decision is subject to approval by the Department. In addition to all other responsibility factors, this contract or deliver and install proposal requires all bidders and all bidder's subcontractors to disclose participation in apprenticeship or training programs that are (1) approved by and registered with the United States Department of Labor's Bureau of Apprenticeship and Training, and (2) applicable to the work of the above indicated proposals or groups. Therefore, all bidders are required to complete the following certification:

1. Except as provided in paragraph 4 below, the undersigned bidder certifies that it is a participant, either as an individual or as part of a group program, in an approved apprenticeship or training program applicable to each type of work or craft that the bidder will perform with its own employees.

2. The undersigned bidder further certifies, for work to be performed by subcontract, that each of its subcontractors either (A) is, at the time of such bid, participating in an approved, applicable apprenticeship or training program; or (B) will, prior to commencement of performance of work pursuant to this contract, establish participation in an approved apprenticeship or training program applicable to the work of the subcontract.

3. The undersigned bidder, by inclusion in the list in the space below, certifies the official name of each program sponsor holding the Certificate of Registration for all of the types of work or crafts in which the bidder is a participant and that will be performed with the bidder's employees. Types of work or craft that will be subcontracted shall be included and listed as subcontract work. The list shall also indicate any type of work or craft job category for which there is no applicable apprenticeship or training program available.

4. Except for any work identified above, if any bidder or subcontractor shall perform all or part of the work of the contract or deliver and install proposal solely by individual owners, partners or members and not by employees to whom the payment of prevailing rates of wages would be required, check the following box, and identify the owner/operator workforces and positions of ownership.

The requirements of this certification and disclosure are a material part of the contract, and the contractor shall require this certification provision to be included in all approved subcontracts. The bidder is responsible for making a complete report and shall make certain that each type of work or craft job category that will be utilized on the project is accounted for and listed. The Department at any time before or afterward may require the production of a copy of each applicable Certificate of Registration issued by the United States Department of Labor evidencing such participation by the contractor and any or all of its subcontractors. In order to fulfill the participation requirement, it shall not be necessary that any applicable program sponsor be currently taking or that it will take applications for apprenticeship, training or employment during the performance of the work of this contract or deliver and install proposal.

Bidder		Signature & Date		
Title				
Address	City		State	Zip Code



Affidavit of Illinois Business Office

Tazewell Washington Rd. (CH 3) 23-00018-06-RS I,Name of Affiant ofCity of Affiant State of Affiant being first duly sworu ponoth, state as follows: City of Affiant State of Affiant 1. That I am theOfficer or Position of	Local Public Agency	County	Str	eet Name/Road Name		Section Number
Name of Affant City of Affant State of Affant being first duly sworn upon oath, state as follows: of	Tazewell County	Tazewell	W	ashington Rd. (CH	3)	23-00018-06-RS
Name of Affant City of Affant State of Affant being first duly sworn upon oath, state as follows: of	I	of				
1. That I am theOfficer or Position	Name of Affiant		Ci	ty of Affiant	,	State of Affiant
Officer or Position Bidder 2. That I have personal knowledge of the facts herein stated. Bidder 3. That, if selected under the proposal described above,	being first duly sworn upon oath, state as follows:					
Officer or Position Officer or Position Bidder 2. That I have personal knowledge of the facts herein stated. 3. That, if selected under the proposal described above,, will maintain a business office State of Illinois, which will be located inCounty 4. That this Atfidavit is given as a requirement of state law as provided in Section 30-22(8) of the Illinois Procurement Code. Signature & Date Print Name of Affiant Print Name of Affiant County Signed (or subscribed or attested) before me on by (date) Bidder Notary Public Signed (or subscribed or attested) before me on by (name/s of person/s) Bidder	1. That I am the	of				
3. That, if selected under the proposal described above,				Bidder		
State of Illinois, which will be located inCounty, Illinois. County Ullinois, County, Illinois, County, Co	2. That I have personal knowledge of the facts her	ein stated.				
State of Illinois, which will be located inCountyCounty, Illinois. CountyCountyCountyCounty for any persons employed in the construction contemplated this proposal. 5. That this Affidavit is given as a requirement of state law as provided in Section 30-22(8) of the Illinois Procurement Code. Signature & Date Print Name of Affiant Print Name of Affiant Signed (or subscribed or attested) before me on by, authorized agent(s), authorized agent(s) Bidder	3. That, if selected under the proposal described a	ibove,			, will ma	intain a business office in the
4. That this business office will serve as the primary place of employment for any persons employed in the construction contemplated this proposal. 5. That this Affidavit is given as a requirement of state law as provided in Section 30-22(8) of the Illinois Procurement Code. Signature & Date Print Name of Affiant Print Name of Affiant County (date) (date) , authorized agent(s) Bidder						
4. That this business office will serve as the primary place of employment for any persons employed in the construction contemplated this proposal. 5. That this Affidavit is given as a requirement of state law as provided in Section 30-22(8) of the Illinois Procurement Code. Signature & Date Print Name of Affiant Print Name of Affiant County			_ County, Illi	nois.		
this proposal. 5. That this Affidavit is given as a requirement of state law as provided in Section 30-22(8) of the Illinois Procurement Code. Signature & Date Print Name of Affiant Print Name of Affiant County		,	les me ent fen e			
5. That this Affidavit is given as a requirement of state law as provided in Section 30-22(8) of the Illinois Procurement Code. Signature & Date Print Name of Affiant Print Name of Affiant County C	-	ry place of emp	loyment for a	any persons employed i	n the cor	istruction contemplated by
Signature & Date Print Name of Affiant Print Name of Affiant County						
Notary Public State of IL County	5. That this Affidavit is given as a requirement of s	tate law as prov			is Procu	rement Code.
Notary Public State of IL County Signed (or subscribed or attested) before me on by, authorized agent(s), authorized agent(s), bidder			S	ignature & Date		
Notary Public State of IL County Signed (or subscribed or attested) before me on by, authorized agent(s), authorized agent(s), bidder						
Notary Public State of IL County Signed (or subscribed or attested) before me on by, authorized agent(s), authorized agent(s), bidder						
Notary Public State of IL County Signed (or subscribed or attested) before me on by, authorized agent(s), authorized agent(s), bidder			P	rint Name of Affiant		
State of IL County Signed (or subscribed or attested) before me on by , authorized agent(s) , authorized agent(s) , Bidder Notary Public Signature & Date						
State of IL County Signed (or subscribed or attested) before me on by , authorized agent(s) , authorized agent(s) , Bidder Notary Public Signature & Date			L			
State of IL County Signed (or subscribed or attested) before me on by , authorized agent(s) , authorized agent(s) , Bidder Notary Public Signature & Date						
State of IL County Signed (or subscribed or attested) before me on by , authorized agent(s) , authorized agent(s) , Bidder Notary Public Signature & Date						
CountySigned (or subscribed or attested) before me on by, authorized agent(s), authorized agent(s), authorized agent(s), Bidder	-					
Signed (or subscribed or attested) before me on by, authorized agent(s), authorized agent(s), authorized agent(s), Bidder	State of IL					
(date), authorized agent(s) Bidder Notary Public Signature & Date	County					
(date), authorized agent(s) Bidder Notary Public Signature & Date	Signed (or subscribed or attested) before me on		by			
(name/s of person/s)Bidder Notary Public Signature & Date		(date)				
Bidder Notary Public Signature & Date					,	authorized agent(s) of
Notary Public Signature & Date	(name	e/s of person/s)				
Notary Public Signature & Date						
	Bidder					
(SEAL) My commission expires				Notary Public S	ignature	& Date
(SEAL) My commission expires						
(SEAL) My commission expires						
				My commission	exnires	
	(SEAL)					

INDEX FOR SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS

Adopted January 1, 2023

This index contains a listing of SUPPLEMENTAL SPECIFICATIONS and frequently used RECURRING SPECIAL PROVISIONS.

ERRATA Standard Specifications for Road and Bridge Construction

(Adopted 1-1-22) (Revised 1-1-23)

SUPPLEMENTAL SPECIFICATIONS

Std. Spe	ec. Sec.	Page No.
202	Earth and Rock Excavation	1
204	Borrow and Furnished Excavation	2
207	Porous Granular Embankment	3
211	Topsoil and Compost	
407	Hot-Mix Asphalt Pavement (Full-Depth)	5
420	Portland Cement Concrete Pavement	6
502	Excavation for Structures	7
509	Metal Railings	8
540	Box Culverts	9
542	Pipe Culverts	
586	Granular Backfill for Structures	34
644	High Tension Cable Median Barrier	35
782	Reflectors	36
801	Electrical Requirements	38
821	Roadway Luminaires	40
1003	Fine Aggregates	41
1004	Coarse Aggregates	42
1020	Portland Cement Concrete	43
1030	Hot-Mix Asphalt	44
1067	Luminaire	45
1097	Reflectors	52



Check Sheet for Recurring Special Provisions

Local Public Agency	County	Section Number
Tazewell County	Tazewell	23-00018-06-RS

Check this box for lettings prior to 01/01/2023.

The Following Recurring Special Provisions Indicated By An "X" Are Applicable To This Contract And Are Included By Reference:

Che	<u>ck Sheet #</u>	<u></u>	<u>Page No</u>
1		Additional State Requirements for Federal-Aid Construction Contracts	53
2		Subletting of Contracts (Federal-Aid Contracts)	56
3		EEO	57
4		Specific EEO Responsibilities Non Federal-Aid Contracts	67
5		Required Provisions - State Contracts	72
6		Asbestos Bearing Pad Removal	78
7		Asbestos Waterproofing Membrane and Asbestos HMA Surface Removal	79
8		Temporary Stream Crossings and In-Stream Work Pads	80
9		Construction Layout Stakes	81
10		Use of Geotextile Fabric for Railroad Crossing	84
11		Subsealing of Concrete Pavements	86
12		Hot-Mix Asphalt Surface Correction	90
13		Pavement and Shoulder Resurfacing	92
14		Patching with Hot-Mix Asphalt Overlay Removal	93
15		Polymer Concrete	95
16		Reserved	97
17		Bicycle Racks	98
18		Temporary Portable Bridge Traffic Signals	100
19		Nighttime Inspection of Roadway Lighting	102
20		English Substitution of Metric Bolts	103
21		Calcium Chloride Accelerator for Portland Cement Concrete	104
22		Quality Control of Concrete Mixtures at the Plant	105
23		Quality Control/Quality Assurance of Concrete Mixtures	113
24		Reserved	129
25		Reserved	130
26		Temporary Raised Pavement Markers	131
27		Restoring Bridge Approach Pavements Using High-Density Foam	132
28		Portland Cement Concrete Inlay or Overlay	135
29		Portland Cement Concrete Partial Depth Hot-Mix Asphalt Patching	139
30		Longitudinal Joint and Crack Patching	142
31		Concrete Mix Design - Department Provided	144
32		Station Numbers in Pavements or Overlays	145

Recurring Special Provisions

Local Public Agency	County	Section Number
Tazewell County	Tazewell	23-00018-06-RS

The Following Local Roads And Streets Recurring Special Provisions Indicated By An "X" Are Applicable To This Contract And Are Included By Reference:

Local Roads And Streets Recurring Special Provisions

Check	Sheet #	<u>ŧ</u>	Page No.
LRS 1		Reserved	147
LRS 2		Furnished Excavation	148
LRS 3	\boxtimes	Work Zone Traffic Control Surveillance	149
LRS 4	\boxtimes	Flaggers in Work Zones	150
LRS 5	\boxtimes	Contract Claims	151
LRS 6	\boxtimes	Bidding Requirements and Conditions for Contract Proposals	152
LRS 7		Bidding Requirements and Conditions for Material Proposals	158
LRS 8		Reserved	164
LRS 9		Bituminous Surface Treatments	165
LRS 10		Reserved	169
LRS 11	\boxtimes	Employment Practices	170
LRS 12	\boxtimes	Wages of Employees on Public Works	172
LRS 13	\boxtimes	Selection of Labor	174
LRS 14		Paving Brick and Concrete Paver Pavements and Sidewalks	175
LRS 15	\boxtimes	Partial Payments	178
LRS 16		Protests on Local Lettings	179
LRS 17	\boxtimes	Substance Abuse Prevention Program	180
LRS 18		Multigrade Cold Mix Asphalt	181
LRS 19		Reflective Crack Control Treatment	182

TABLE OF CONTENTS

SPECIAL PROVISIONS

Description of Work .								1
Traffic Control Plan .								1
Sequence of Operations.								2
Incidental Hot-Mix Asphalt Surfacing								2
Aggregate Shoulders, Type B (Special).							2
Short Term Pavement Marking								3
Weight Limits			•					3
General Notes			•					3
Wages of Employees on Public Works			•					3
Requirements When Working with the	Railroad							3
Hot-Mix Asphalt Surface Removal.								4-6
BDE SPECIAL PROVISIONS .								7-23
LRS SPECIAL PROVISIONS .								24-29
LOCATION MAP								30
SUMMARY OF QUANTITIES .								31
QUANTITY SHEETS								32-33
TYPICAL CROSS SECTION .								34
STANDARD FOR HMA SURFACING	AT SIDE	ROADS	, ENTRA	ANCES,	AND MA	AILBOXE	ES	35
HIGHWAY STANDARD 406101-D4								36-38
HIGHWAY STANDARD 701006 .								39
HIGHWAY STANDARD 701011 .								40
HIGHWAY STANDARD 701201.								41
HIGHWAY STANDARD 701301.								42
HIGHWAY STANDARD 701306 .								43
HIGHWAY STANDARD 701326 .								44
HIGHWAY STANDARD 701901 .								45-47
HIGHWAY STANDARD 781001 . Revised 2/23/2023								48





Local Public Agency	County	Section Number
Tazewell County	Tazewell	23-00018-06-RS

The following Special Provision supplement the "Standard Specifications for Road and Bridge Construction", adopted

January 1, 2022

, the latest edition of the "Manual on Uniform Traffic Control Devices for Streets and Highways", and the "Manual of Test Procedures of Materials" in effect on the date of invitation of bids, and the Supplemental Specification and Recurring Special Provisions indicated on the Check Sheet included here in which apply to and govern the construction of the above named section, and in case of conflict with any parts, or parts of said Specifications, the said Special Provisions shall take precedence and shall govern.

DESCRIPTION OF WORK: The work of this section consists of hot-mix asphalt surface removal and resurfacing work on Washington Rd. (CH 3) in Tazewell County.

TRAFFIC CONTROL PLAN: Traffic Control shall be in accordance with the applicable sections of the Standard Specifications for Road and Bridge Construction, the applicable guidelines contained in the Illinois Manual on Uniform Traffic Control Devices for Streets and Highways, these Special Provisions, and any special details and Highway Standards contained herein and in the plans and the Standard Specifications for Traffic Control Items.

At the pre-construction meeting, the Contractor shall furnish the name of the individual in his direct employ who is to be responsible for the installation and maintenance of the traffic control for this project. If the actual installation and maintenance are to be accomplished by a subcontractor, consent shall be requested of the Engineer at the time of the pre-construction meeting in accordance with Article 108.01 of the Standard Specifications for Road and Bridge Construction. This shall not relieve the Contractor of the foregoing requirement for a responsible individual in his direct employ. The County will provide the Contractor the name of its representative who will be responsible for the administration of the Traffic Control Plan. Special attention is called to Articles 107.09, 107.14, 107.15, 1095.06, 1106 of the Standard Specifications for Road and Bridge Construction and the and Bridge Construction and the following Highway Standards and Special Provisions relating to Traffic Control.

Special attention is also called to the Highway Standards, 701006, 701011, 701201, 701301, 701306, and 701901 contained herein.

The entire project shall be kept open to through traffic.

"NO PASSING ZONES NOT STRIPED NEXT MILES" signs shall be posted in accordance with Article 701.17.

The presence of temporary traffic control drawings or standards in the proposal or contract, whether a pay item or not, does not relieve the Contractor of his obligation to the public. The Contractor shall provide, if conditions warrant by the Engineer, all protection deemed necessary beyond that shown in the proposal or Special Provisions.

Construction signs shall meet the current Standard Specifications for Traffic Control Items.

Basis of Payment: All required Traffic Control shall be paid for at the contract-lump sum price for TRAFFIC CONTROL AND PROTECTION, (SPECIAL).

Local Public Agency	County	Section Number
Tazewell County	Tazewell	23-00018-06-RS

SEQUENCE OF OPERATIONS: The Contractor shall first place CLASS D PATCHES, TYPE IV, 6" (SPECIAL) and leave the patch 1.5" below existing surface. The patches shall then be following by the HOT-MIX ASPHALT SURFACE REMOVAL, 1.5" to bring the entire roadway to the same elevation as the top of the new CLASS D PATCHES, TYPE IV, 6" (SPECIAL). After the surface is milled the roadway and shoulders shall be primed and resurfaced as shown on the typical cross section. This schedule of operations may be changed with the approval of the Engineer. The items of work shall be paid for at the contract unit prices of the various pay items for the work involved and no additional compensation will be allowed if the schedule of operations is changed.

CLASS D PATCHES, TYPE IV, 6" (SPECIAL): Section 442 of the Standard Specifications shall apply with the following changes and stipulations:

The depth of pavement removal shall be 7.5" from the top of the existing surface. The top of the 6 inch patch shall be 1.5" below the existing surface.

INCIDENTAL HOT-MIX ASPHALT SURFACING: Any preparation required prior to construction of INCIDENTAL HOT-MIX ASPHALT SURFACING will not be measured separately but shall be included in the contract unit price per ton for INCIDENTAL HOT-MIX ASPHALT SURFACING. To prevent damage to newly constructed bituminous surfaces, it is understood that an interval of up to one week shall lapse before incidental hot-mix asphalt surfacing operations begin, depending on weather and curing conditions, as directed by the Engineer.

AGGREGATE SHOULDERS, TYPE B (SPECIAL): This work shall be constructed in accordance with Article 481 of the Standard Specifications with the following exceptions and additions:

Revise Note 1 of Article 481.02 to the following: Note 1. Reclaimed asphalt pavement (RAP) may be used as AGGREGATE SHOULDERS, TYPE B (SPECIAL).

This work will include entrance radii and transitions to existing aggregate and earth entrances. Material placed at entrances shall be of the same type and gradation as the existing entrance except in the case of earth field entrances where a transition of aggregate shall be placed to provide safe entrance to the bituminous roadway.

Areas that are not accessible by mechanical spreader during normal shoulder operations will be constructed by handwork as necessary by any method that provides a usable surface and has a uniform and neat appearance and shall be compacted by a means approved by the Engineer.

No extra compensation will be allowed for handwork required to complete shoulders along roadway, entrances, or at driveway transitions.

To prevent damage to newly constructed bituminous surfaces, it is understood that an interval of up to two weeks shall lapse before shoulder operations begin, depending on weather and curing conditions.

Revise Article 481.10 to read: Basis of Payment. This work will be paid for at the contract unit price per ton for AGGREGATE SHOULDERS, TYPE B (SPECIAL).

Local Public Agency	County	Section Number
Tazewell County	Tazewell	23-00018-06-RS

<u>SHORT TERM PAVEMENT MARKING</u>: Section 703 of the Standard Specifications shall apply with the following changes and stipulations:

Permanent pavement markings will be applied by others, therefore the Contractor will not be responsible for replacing short - term markings with temporary or permanent pavement markings. The Contractor will be responsible for maintaining short term markings for 30 days or until permanent pavement markings are applied whichever is first.

Article 703.02 Materials. Material shall be pavement marking tape as specified.

Revise Article 703.07 to read: Basis of Payment. This work will be paid for at the contract unit price per foot for SHORT TERM PAVEMENT MARKING.

Removal of short term pavement markings will be paid for at the contract unit price per square foot for SHORT TERM PAVEMENT MARKING REMOVAL.

<u>WEIGHT LIMITS</u>: Legal weight limits shall be observed on Tazewell County highways and the structures they contain at all times. The Contractor shall apply for overweight and over dimension permits in advance to avoid delays in work.

<u>GENERAL NOTES</u>: Where section or subsection monuments are encountered, the Engineer shall be notified before such monuments are removed. The Contractor shall protect and carefully preserve all property markers and monuments until the owner, and authorized surveyor or agent has witnessed or otherwise referenced their location.

WAGES OF EMPLOYEES ON PUBLIC WORKS: Add the following to paragraph #1 of the Special Provision for Wages of Employees on Public Works, Check Sheet LRS#12: Prevailing wage rates may be obtained from the IDOL (Illinois Department of Labor) website at:

https://www2.illinois.gov/idol/Laws-Rules/CONMED/Pages/Rates.aspx

REQUIREMENTS WHEN WORKING WITH THE RAILROAD

Effective: April 1, 2016 Revised: April 1, 2022

Special attention is brought to Section 100 of the "Standard Specifications for Road and Bridge Construction" regarding working with the Railroad and the authority of the Railroad Engineer as defined. The Contractor shall make themselves aware of all the rules and regulations the railroad may have regarding, but not limited to, working restrictions, safety training, safety procedures and flagger scheduling and call-off requirements. The Contractor shall also submit, to the Railroad, copies, for review and approval, any work plans that may directly impact the Railroad facilities. This submittal shall happen concurrently when submitting to the Department.

Responsibility for flagger costs shall be in accordance with Article 107.12 of the Standard Specifications. The cost to comply with any other requirements the Railroad may have in order to perform work on this project shall be considered included in the cost of the contract items and no additional compensation will be allowed.

Local Public Agency	County	Section Number
Tazewell County	Tazewell	23-00018-06-RS

HOT-MIX ASPHALT SURFACE REMOVAL

Effective: March 1, 1993 Revised: January 1, 2022

Description: This work shall consist of removing a portion of the existing hot-mix asphalt concrete surface course in accordance with the applicable portions of Section 440 and 1101 of the Standard Specifications, this special provision, details in the plans and as directed by the Engineer. The cold milled salvaged aggregate resulting from this operation shall remain the property of the Tazewell County Highway Department and shall be transported to the Tazewell County maintenance yard in Tremont, IL. Other sites may be determined by mutual agreement between the Contractor and the County. If other sites are approved, the Contractor will be responsible for preventing theft of milled material or unauthorized removal of said material from sites other than County property.

Equipment: The machine used for milling and planing shall be a self-propelled grinding machine having a minimum 12' (3.6 m) wide drum at least 28" (710 mm) in diameter. When a milling width in excess of 12' is required and the Contractor's milling machine is less than the required width shown in the plans, the remaining area shall be milled with a machine capable of meeting the requirements of this special provision. Milling attachments used with skid steer tractors will not be allowed for longitudinal areas to mill additional widths.

When the teeth become worn so that they do not produce a uniform surface texture, they shall all be changed at the same time (as a unit). Occasionally, individual teeth may be changed if they lock up or break, but this method shall not be used to avoid changing the set of teeth as a unit. Occasional gouges, due to deteriorated pavement condition, or separation of lifts will not be cause to replace all teeth. The Engineer will be the sole judge of the cause of the pavement gouging and the corrective work required. Corrective work due to negligence or poor workmanship shall be at the Contractor's expense.

The moldboard is critical in obtaining the desired surface texture. It shall be straight, true, and free of excessive nicks or wear, and it shall be replaced as necessary to uniformly produce the required surface texture. Gouging of the pavement by more than 1/4 inch (6 mm) shall be sufficient cause to require replacement of all teeth.

Construction Requirements

General: Weather conditions, when milling work is performed, must be such that short term or temporary pavement markings can be placed the day the surface is milled in accordance with Section 703 "Work Zone Pavement Markings".

An automatic grade control device shall be used when milling mainline pavement and shall be capable of controlling the elevation of the drum relative to either a preset grade control stringline or a grade reference device traveling on the adjacent pavement surface. The automatic grade control device may be utilized only on one side of the machine with a automatic slope control device controlling the opposite side. The traveling grade reference device shall not be less than 30 feet (9 m) in length. When milling cross roads, turn lanes, intersections, crossovers, or other miscellaneous areas, the Engineer may permit the matching shoe. The Contractor, at his option, may also substitute an approved 6' wide (1.8 m) machine for areas other than mainline pavement.

Local Public Agency	County	Section Number
Tazewell County	Tazewell	23-00018-06-RS

The Contractor shall mill a depth according to the plans herein at the centerline and project the proposed cross slope to the edge of pavement. In the event the milling at the outer edge of the lane would exceed 2 inches; then the Contractor shall reduce the cut at the centerline to provide the maximum cut of 1.75 inches at the edge of pavement. If deemed necessary, the Contractor may reduce the cross slope from normal 1.5% to 1%.

Surface tests will be performed in accordance with Article 406.11 of the Standard Specifications. The longitudinal profile will be taken 3 ft. (0.9 m) from and parallel to each edge of pavement and 3 ft. (0.9 m) from and parallel to the centerline on each side. If a shadow area is found at the 3 ft. (0.9 m) points the pavement smoothness tester will be moved sufficient distance either side to measure the Contractor's milling efforts. Any surface variations exceeding the tolerance in Article 406.11 shall be corrected by reprofiling at no additional expense to the Department. In addition, the Contractor shall be responsible for refilling with approved hot-mix asphalt mixtures any area that lowered the pavement profile as a result of faulty milling operations if directed by the Engineer. The Contractor shall be responsible for providing the pavement smoothness tester described elsewhere to retest the pavement profile obtained.

If the milling depth is intended to expose the original concrete pavement, then additional hand or machine work may be necessary to remove any remaining veneer of bituminous pavement which may be left in place behind the milling machine. Such work will be at the direction of the Engineer and at no extra cost to the Department.

The Contractor shall provide a 10 foot (3 m) straightedge equipped with a carpenter's level or a 7 foot (2.1 m) electronic straightedge to check the cross slope of the roadway at regular intervals as directed by the Engineer.

Surface Texture: Each tooth on the cutting drum shall produce a series of discontinuous longitudinal striations. There shall be 16 to 20 striations (tooth marks) for each tooth for each 6 feet (1.8 m) in the longitudinal direction, and each striation shall be 1.7 inches \pm 0.2 inch (43 \pm 5 mm) in length after the area is planed by the moldboard. Thus, the planed length between each pair of striations shall be 2.3 inches \pm 0.2 inch (58 \pm 5 mm). There shall be 80 to 96 rows of discontinuous longitudinal striations for each 5 feet (1.5 m) in the transverse dimension. The areas between the striations in both the longitudinal and transverse directions shall be flat topped and coplaner. The moldboard shall be used to cut this plane; and any time the operation fails to produce this flat plane interspersed with a uniform pattern of discontinuous longitudinal striations, the operation shall be stopped and the cause determined and corrected before recommencing. Other similar patterns of uniform discontinuous longitudinal striations interspersed on a flat plane may be approved by the Engineer. The drawing titled "Hot-Mix Asphalt Surface Removal" showing the desired surface texture is included in the plans.

The start-up milling speed shall be limited to a maximum of 50 foot (15 m) per minute. The Contractor shall limit his operations to this speed to demonstrate his ability to obtain the striations and ride ability as described above. If the Contractor is able to demonstrate that he can consistently obtain the desired striations and ride ability at a greater speed he will be permitted to run at the increased speed.

Cleanup: After cold milling a traffic lane and before opening the lane to traffic, the pavement shall be swept by a mechanical broom to prevent compaction of the cuttings onto the pavement. All loose material shall be removed from the roadway. Before the prime coat is placed, the pavement shall be cleaned of all foreign material to the satisfaction of the Engineer.

Local Public Agency	County	Section Number
Tazewell County	Tazewell	23-00018-06-RS

This cleanup work shall be considered included in the contract unit price per Square Meter (Square Yard) for HOT-MIX ASPHALT SURFACE REMOVAL of the depth specified, and no additional compensation will be allowed.

Method of Measurement:

(a) Contract Quantities. The requirements for the use of Contract Quantities shall be Article 202.07(a) of the Standard Specifications.

(b) Measured Quantities. Cold milling and planing will be measured and the area computed in square yards (square meters) of surface.

Areas not milled (shadowed areas) due to rutting in the existing pavement surface will be included in the area measured for payment.

Basis of Payment: The cold milling and planing will be paid for at the contract unit price per Square Yard (Square Meter) for HOT-MIX ASPHALT SURFACE REMOVAL of the depth specified. Payment as specified will include variations in depth of cuts due to rutting, superelevations, and pavement crown and no additional compensation will be allowed.

BDE SPECIAL PROVISIONS For the April 28, 2023 and June 16, 2023 Lettings

The following special provisions indicated by a "check mark" are applicable to this contract and will be included by the Project Coordination and Implementation Section of the Bureau of Design & Environment (BDE).

Fi	e Name	#		Special Provision Title	Effective	Revised
	80099			Accessible Pedestrian Signals (APS)	April 1, 2003	Jan. 1, 2022
	80274	2	\square	Aggregate Subgrade Improvement	April 1, 2012	April 1, 2022
	80192	3		Automated Flagger Assistance Devices	Jan. 1, 2008	April 1, 2023
	80173	4		Bituminous Materials Cost Adjustments	Nov. 2, 2006	Aug. 1, 2017
	80426	5		Bituminous Surface Treatment with Fog Seal	Jan. 1, 2020	Jan. 1, 2022
	80436	6		Blended Finely Divided Minerals	April 1, 2021	
*	80241	7		Bridge Demolition Debris	July 1, 2009	
*	5053I	8		Building Removal	Sept. 1, 1990	Aug. 1, 2022
*	5026I	9		Building Removal with Asbestos Abatement	Sept. 1, 1990	Aug. 1, 2022
	80384	10	\checkmark	Compensable Delay Costs	June 2, 2017	April 1, 2019
*	80198	11		Completion Date (via calendar days)	April 1, 2008	
*	80199	12		Completion Date (via calendar days) Plus Working Days	April 1, 2008	
	80261	13		Construction Air Quality – Diesel Retrofit	June 1, 2010	Nov. 1, 2014
	80434	14		Corrugated Plastic Pipe (Culvert and Storm Sewer)	Jan. 1, 2021	
*	80029	15		Disadvantaged Business Enterprise Participation	Sept. 1, 2000	Mar. 2, 2019
	80229	16		Fuel Cost Adjustment	April 1, 2009	Aug. 1, 2017
	80447	17		Grading and Shaping Ditches	Jan. 1, 2023	
	80433	18		Green Preformed Thermoplastic Pavement Markings	Jan. 1, 2021	Jan. 1, 2022
	80443	19		High Tension Cable Median Barrier Removal	April 1, 2022	
	80446			Hot-Mix Asphalt - Longitudinal Joint Sealant	Nov. 1, 2022	
	80438			Illinois Works Apprenticeship Initiative – State Funded Contracts	June 2, 2021	Sept. 2, 2021
	80045		\checkmark	Material Transfer Device	June 15, 1999	Jan. 1, 2022
	80441		\checkmark	Performance Graded Asphalt Binder	Jan. 1, 2023	
*		24		Railroad Protective Liability Insurance	Dec. 1, 1986	Jan. 1, 2022
	80445			Seeding	Nov. 1, 2022	
	80448			Source of Supply and Quality Requirements	Jan. 2, 2023	
	80340		Ц	Speed Display Trailer	April 2, 2014	Jan. 1, 2022
	80127		Ц	Steel Cost Adjustment	April 2, 2004	Jan. 1, 2022
	80397		Ц	Subcontractor and DBE Payment Reporting	April 2, 2018	
	80391		\square	Subcontractor Mobilization Payments	Nov. 2, 2017	April 1, 2019
	80437		Ц	Submission of Payroll Records	April 1, 2021	Nov. 1, 2022
	80435		Ц	Surface Testing of Pavements – IRI	Jan. 1, 2021	Jan. 1, 2023
	80410			Traffic Spotters	Jan. 1, 2019	
*	20338		Ц	Training Special Provisions	Oct. 15, 1975	Sept. 2, 2021
	80429			Ultra-Thin Bonded Wearing Course	April 1, 2020	Jan. 1, 2022
		36	\checkmark	Vehicle and Equipment Warning Lights	Nov. 1, 2021	Nov. 1, 2022
	80440		Ц	Waterproofing Membrane System	Nov. 1, 2021	
	80302		Ц	Weekly DBE Trucking Reports	June 2, 2012	Nov. 1, 2021
*		39		Work Zone Traffic Control Devices	Mar. 2, 2020	
^	80071	40	\checkmark	Working Days	Jan. 1, 2002	

Highlighted items indicate a new or revised special provision for the letting.

An * indicates the special provision requires additional information from the designer, which needs to be submitted separately. The Project Coordination and Implementation Section will then include the information in the applicable special provision.

The following special provisions have been deleted from use.

File Name	Special Provision Title	Effective Revised
50481	Building Removal-Case II (Non-Friable Asbestos)	Sept. 1, 1990 April 1, 2010
50491	Building Removal-Case III (Friable Asbestos)	Sept. 1, 1990 April 1, 2010

The following special provisions are in the 2023 Supplemental Specifications and Recurring Special Provisions.

File Name 80293	<u>Special Provision Title</u> Concrete Box Culverts with Skews > 30 Degrees and Design Fills ≤ 5 Feet	<u>New Location(s)</u> Articles 540.04 & 540.06	<u>Effective</u> April 1, 2012	<u>Revised</u> July 1, 2016
80311	Concrete End Sections for Pipe Culverts	Articles 540.07, 542.01, 542.02, 542.07, 542.11 & 542.12	Jan. 1, 2013	April 1, 2016
80422	High Tension Cable Median Barrier	Articles 644.02, 644.05, 782.01, 782.04, 782.07 & 1097.02	Jan. 1, 2020	Jan. 1, 2022
80442	Hot-Mix Asphalt	Articles 1030.09 & 1030.10	Jan. 1, 2022	Aug. 1, 2022
80444	Hot-Mix Asphalt – Patching	Errata – Article 442.08(b)	April 1, 2022	-
80411	Luminaires, LED	Articles 801.05(a), 821.02(d), 821.03, 821.08 & 1067.01-1067.06	April 1, 2019	Jan. 1, 2022
80418	Mechanically Stabilized Earth Retaining Walls	Articles 1003.07 & 1004.06	Nov. 1, 2019	Nov. 1, 2020
80430	Portland Cement Concrete – Haul Time	Article 1020.11(a)(7)	July 1, 2020	
80395	Sloped Metal End Section for Pipe Culverts	Articles 540.07, 542.01, 542.02, 542.07, 542.11 & 542.12	Jan. 1, 2018	
80318	Traversable Pipe Grate for Concrete End Sections	Articles 540.04, 540.07, 540.08 & 542.01, 542.02, 542.07, 542.11 & 542.12	Jan. 1, 2013	Jan. 1, 2018

COMPENSABLE DELAY COSTS (BDE)

Effective: June 2, 2017 Revised: April 1, 2019

Revise Article 107.40(b) of the Standard Specifications to read:

- "(b) Compensation. Compensation will not be allowed for delays, inconveniences, or damages sustained by the Contractor from conflicts with facilities not meeting the above definition; or if a conflict with a utility in an unanticipated location does not cause a shutdown of the work or a documentable reduction in the rate of progress exceeding the limits set herein. The provisions of Article 104.03 notwithstanding, compensation for delays caused by a utility in an unanticipated location will be paid according to the provisions of this Article governing minor and major delays or reduced rate of production which are defined as follows.
 - (1) Minor Delay. A minor delay occurs when the work in conflict with the utility in an unanticipated location is completely stopped for more than two hours, but not to exceed two weeks.
 - (2) Major Delay. A major delay occurs when the work in conflict with the utility in an unanticipated location is completely stopped for more than two weeks.
 - (3) Reduced Rate of Production Delay. A reduced rate of production delay occurs when the rate of production on the work in conflict with the utility in an unanticipated location decreases by more than 25 percent and lasts longer than seven calendar days."

Revise Article 107.40(c) of the Standard Specifications to read:

- "(c) Payment. Payment for Minor, Major, and Reduced Rate of Production Delays will be made as follows.
 - (1) Minor Delay. Labor idled which cannot be used on other work will be paid for according to Article 109.04(b)(1) and (2) for the time between start of the delay and the minimum remaining hours in the work shift required by the prevailing practice in the area.

Equipment idled which cannot be used on other work, and which is authorized to standby on the project site by the Engineer, will be paid for according to Article 109.04(b)(4).

(2) Major Delay. Labor will be the same as for a minor delay.

Equipment will be the same as for a minor delay, except Contractor-owned equipment will be limited to two weeks plus the cost of move-out to either the

Contractor's yard or another job and the cost to re-mobilize, whichever is less. Rental equipment may be paid for longer than two weeks provided the Contractor presents adequate support to the Department (including lease agreement) to show retaining equipment on the job is the most economical course to follow and in the public interest.

(3) Reduced Rate of Production Delay. The Contractor will be compensated for the reduced productivity for labor and equipment time in excess of the 25 percent threshold for that portion of the delay in excess of seven calendar days. Determination of compensation will be in accordance with Article 104.02, except labor and material additives will not be permitted.

Payment for escalated material costs, escalated labor costs, extended project overhead, and extended traffic control will be determined according to Article 109.13."

Revise Article 108.04(b) of the Standard Specifications to read:

- "(b) No working day will be charged under the following conditions.
 - (1) When adverse weather prevents work on the controlling item.
 - (2) When job conditions due to recent weather prevent work on the controlling item.
 - (3) When conduct or lack of conduct by the Department or its consultants, representatives, officers, agents, or employees; delay by the Department in making the site available; or delay in furnishing any items required to be furnished to the Contractor by the Department prevents work on the controlling item.
 - (4) When delays caused by utility or railroad adjustments prevent work on the controlling item.
 - (5) When strikes, lock-outs, extraordinary delays in transportation, or inability to procure critical materials prevent work on the controlling item, as long as these delays are not due to any fault of the Contractor.
 - (6) When any condition over which the Contractor has no control prevents work on the controlling item."

Revise Article 109.09(f) of the Standard Specifications to read:

"(f) Basis of Payment. After resolution of a claim in favor of the Contractor, any adjustment in time required for the work will be made according to Section 108. Any adjustment in the costs to be paid will be made for direct labor, direct materials, direct equipment, direct jobsite overhead, direct offsite overhead, and other direct costs allowed by the resolution. Adjustments in costs will not be made for interest charges, loss of anticipated profit, undocumented loss of efficiency, home office overhead and unabsorbed overhead other than as allowed by Article 109.13, lost opportunity, preparation of claim expenses and other consequential indirect costs regardless of method of calculation.

The above Basis of Payment is an essential element of the contract and the claim cost recovery of the Contractor shall be so limited."

Add the following to Section 109 of the Standard Specifications.

"**109.13 Payment for Contract Delay.** Compensation for escalated material costs, escalated labor costs, extended project overhead, and extended traffic control will be allowed when such costs result from a delay meeting the criteria in the following table.

Contract Type Cause of Delay		Length of Delay	
Working Days	Article 108.04(b)(3) or Article 108.04(b)(4)	No working days have been charged for two consecutive weeks.	
Completion Date	Article 108.08(b)(1) or Article 108.08(b)(7)	The Contractor has been granted a minimum two week extension of contract time, according to Article 108.08.	

Payment for each of the various costs will be according to the following.

- (a) Escalated Material and/or Labor Costs. When the delay causes work, which would have otherwise been completed, to be done after material and/or labor costs have increased, such increases will be paid. Payment for escalated material costs will be limited to the increased costs substantiated by documentation furnished by the Contractor. Payment for escalated labor costs will be limited to those items in Article 109.04(b)(1) and (2), except the 35 percent and 10 percent additives will not be permitted.
- (b) Extended Project Overhead. For the duration of the delay, payment for extended project overhead will be paid as follows.
 - (1) Direct Jobsite and Offsite Overhead. Payment for documented direct jobsite overhead and documented direct offsite overhead, including onsite supervisory and administrative personnel, will be allowed according to the following table.

Original Contract Amount	Supervisory and Administrative Personnel
Up to \$5,000,000	One Project Superintendent
Over \$ 5,000,000 - up to \$25,000,000	One Project Manager, One Project Superintendent or Engineer, and One Clerk
Over \$25,000,000 - up to \$50,000,000	One Project Manager, One Project Superintendent, One Engineer, and

	One Clerk
Over \$50,000,000	One Project Manager, Two Project Superintendents,
Over \$30,000,000	One Engineer, and One Clerk

- (2) Home Office and Unabsorbed Overhead. Payment for home office and unabsorbed overhead will be calculated as 8 percent of the total delay cost.
- (c) Extended Traffic Control. Traffic control required for an extended period of time due to the delay will be paid for according to Article 109.04.

When an extended traffic control adjustment is paid under this provision, an adjusted unit price as provided for in Article 701.20(a) for increase or decrease in the value of work by more than ten percent will not be paid.

Upon payment for a contract delay under this provision, the Contractor shall assign subrogation rights to the Department for the Department's efforts of recovery from any other party for monies paid by the Department as a result of any claim under this provision. The Contractor shall fully cooperate with the Department in its efforts to recover from another party any money paid to the Contractor for delay damages under this provision."

80384

Project Coordination and Implementation Section will include a copy in the contract.

80045m

MATERIAL TRANSFER DEVICE (BDE)

Effective: June 15, 1999 Revised: January 1, 2022

Add the following to Article 406.03 of the Standard Specifications:

"(n) Material Transfer Device1102.02"

Add the following to the end of Article 406.06(f) of the Standard Specifications:

"When required, a material transfer device (MTD) shall be used to transfer the HMA from the haul trucks to the spreading and finishing machine. The particular HMA mixtures for which an MTD is required will be specified in the plans. When not required, an MTD may still be used at the Contractor's option, subject to the requirements and restrictions herein. Use of MTDs shall be according to the following.

MTD Category	Usage
Category I	Any resurfacing application Full-Depth HMA where the in-place binder thickness is ≥ 10 in. (250 mm)
Category II	Full-Depth HMA where the in-place binder thickness is < 10 in. (250 mm)

Category I MTD's will only be allowed to travel over structures under the following conditions:

- (1) Approval will be given by the Engineer.
- (2) The MTD shall be emptied of HMA material prior to crossing the structure and shall travel at crawl speed across the structure.
- (3) The tires of the MTD shall travel on or in close proximity and parallel to the beam and/or girder lines of the structure."

Add the following to the end of Article 406.13(b) of the Standard Specifications:

"The required use of an MTD will be measured for payment in tons (metric tons) of the HMA mixtures placed with the MTD. The use of an MTD at the Contractor's option will not be measured for payment."

Add the following between the second and third paragraphs of Article 406.14 of the Standard Specifications:

"The required use of an MTD will be paid for at the contract unit price per ton (metric ton) for MATERIAL TRANSFER DEVICE. The HMA mixtures placed with the MTD will be paid for separately according to their respective specifications."

Revise Article 1102.02 of the Standard Specifications to read:

"1102.02 Material Transfer Device (MTD). The MTD shall be according to the following.

- (a) Requirements. The MTD shall have a minimum surge capacity of 15 tons (13.5 metric tons), shall be self-propelled and capable of moving independent of the paver, and shall be equipped with the following.
 - (1) Front-Dump Hopper and Conveyor. The conveyor shall provide a positive restraint along the sides of the conveyor to prevent material spillage. MTDs having paver style hoppers shall have a horizontal bar restraint placed across the foldable wings which prevents the wings from being folded.
 - (2) Paver Hopper Insert. The paver hopper insert shall have a minimum capacity of 14 tons (12.7 metric tons).
 - (3) Mixer/Agitator Mechanism. This re-mixing mechanism shall consist of a segmented, anti-segregation, re-mixing auger.
- (b) Qualification and Designation. The MTD shall be on the Department's qualified product list with one of the following designations.
 - (1) Category I. The MTD has a documented maximum HMA carrying capacity contact pressure greater than 25 psi and has a central surge hopper of sufficient capacity to mix upstream HMA with downstream HMA.
 - (2) Category II. The MTD has a documented maximum HMA carrying capacity contact pressure less than or equal to 25 psi."

80045

PERFORMANCE GRADED ASPHALT BINDER (BDE)

Effective: January 1, 2023

Revise Article 1032.05 of the Standard Specifications to read:

"1032.05 Performance Graded Asphalt Binder. These materials will be accepted according to the Bureau of Materials Policy Memorandum, "Performance Graded Asphalt Binder Qualification Procedure." The Department will maintain a qualified producer list. These materials shall be free from water and shall not foam when heated to any temperature below the actual flash point. Air blown asphalt, recycle engine oil bottoms (ReOB), and polyphosphoric acid (PPA) modification shall not be used.

When requested, producers shall provide the Engineer with viscosity/temperature relationships for the performance graded asphalt binders delivered and incorporated in the work.

(a) Performance Graded (PG) Asphalt Binder. The asphalt binder shall meet the requirements of AASHTO M 320, Table 1 "Standard Specification for Performance Graded Asphalt Binder" for the grade shown on the plans and the following.

Test	Parameter
Small Strain Parameter (AASHTO PP 113) BBR, ΔTc, 40 hrs PAV (40 hrs continuous or 2 PAV at 20 hrs)	-5 °C min.

(b) Modified Performance Graded (PG) Asphalt Binder. The asphalt binder shall meet the requirements of AASHTO M 320, Table 1 "Standard Specification for Performance Graded Asphalt Binder" for the grade shown on the plans.

Asphalt binder modification shall be performed at the source, as defined in the Bureau of Materials Policy Memorandum, "Performance Graded Asphalt Binder Qualification Procedure."

Modified asphalt binder shall be safe to handle at asphalt binder production and storage temperatures or HMA construction temperatures. Safety Data Sheets (SDS) shall be provided for all asphalt modifiers.

(1) Polymer Modification (SB/SBS or SBR). Elastomers shall be added to the base asphalt binder to achieve the specified performance grade and shall be either a styrene-butadiene diblock, triblock copolymer without oil extension, or a styrenebutadiene rubber. The polymer modified asphalt binder shall be smooth, homogeneous, and be according to the requirements shown in Table 1 or 2 for the grade shown on the plans.

Table 1 - Requirements for Styrene-Butadiene Copolymer (SB/SBS) Modified Asphalt Binders			
Test	Asphalt Grade SB/SBS PG 64-28 SB/SBS PG 70-22	Asphalt Grade SB/SBS PG 64-34 SB/SBS PG 70-28 SB/SBS PG 76-22 SB/SBS PG 76-28	
Separation of Polymer ITP, "Separation of Polymer from Asphalt Binder" Difference in °F (°C) of the softening point between top and bottom portions	4 (2) max.	4 (2) max.	
point between top and bettern pertone	- (2) max.	- (2) max.	
TESTS ON RESIDUE FROM ROLLING THIN FILM OVEN TEST (AASHTO T 240)			
Elastic Recovery ASTM D 6084, Procedure A, 77 °F (25 °C), 100 mm elongation, %	60 min.	70 min.	

Table 2 - Requirements for Styrene-Butadiene Rubber (SBR) Modified Asphalt Binders			
Test	Asphalt Grade SBR PG 64-28 SBR PG 70-22	Asphalt Grade SB/SBS PG 64-34 SB/SBS PG 70-28 SBR PG 76-22 SBR PG 76-28	
Separation of Polymer ITP, "Separation of Polymer from Asphalt Binder" Difference in °F (°C) of the softening point between top and bottom portions	4 (2) max.	4 (2) max.	
Toughness ASTM D 5801, 77 °F (25 °C), 20 in./min. (500 mm/min.), inlbs (N-m)	110 (12.5) min.	110 (12.5) min.	
Tenacity ASTM D 5801, 77 °F (25 °C), 20 in./min. (500 mm/min.), inlbs (N-m)	75 (8.5) min.	75 (8.5) min.	
TESTS ON RESIDUE FROM ROLLING THIN FILM OVEN TEST (AASHTO T 240)			
Elastic Recovery ASTM D 6084, Procedure A, 77 °F (25 °C), 100 mm elongation, %	40 min.	50 min.	

(2) Ground Tire Rubber (GTR) Modification. GTR modification is the addition of recycled ground tire rubber to liquid asphalt binder to achieve the specified performance grade. GTR shall be produced from processing automobile and/or truck tires by the ambient

grinding method or micronizing through a cryogenic process. GTR shall not exceed 1/16 in. (2 mm) in any dimension and shall not contain free metal particles, moisture that would cause foaming of the asphalt, or other foreign materials. A mineral powder (such as talc) meeting the requirements of AASHTO M 17 may be added, up to a maximum of four percent by weight of GTR to reduce sticking and caking of the GTR particles. When tested in accordance with Illinois Modified AASHTO T 27 "Standard Method of Test for Sieve Analysis of Fine and Coarse Aggregates" or AASHTO PP 74 "Standard Practice for Determination of Size and Shape of Glass Beads Used in Traffic Markings by Means of Computerized Optical Method", a 50 g sample of the GTR shall conform to the following gradation requirements.

Sieve Size	Percent Passing
No. 16 (1.18 mm)	100
No. 30 (600 μm)	95 ± 5
No. 50 (300 μm)	> 20

GTR modified asphalt binder shall be tested for rotational viscosity according to AASHTO T 316 using spindle S27. GTR modified asphalt binder shall be tested for original dynamic shear and RTFO dynamic shear according to AASHTO T 315 using a gap of 2 mm.

The GTR modified asphalt binder shall meet the requirements of Table 3.

Table 3 - Requirements for Ground Tire Rubber (GTR) Modified Asphalt Binders					
Test Asphalt Grade Asphalt Grade GTR PG 64-28 GTR PG 76-22 GTR PG 70-22 GTR PG 76-28 GTR PG 70-28					
TESTS ON RESIDUE FROM ROLLING THIN FILM OVEN TEST (AASHTO T 240)					
Elastic Recovery ASTM D 6084, Procedure A, 77 °F (25 °C), 100 mm elongation, %60 min.70 min.					

(3) Softener Modification (SM). Softener modification is the addition of organic compounds, such as engineered flux, bio-oil blends, modified vegetable oils, glycol amines, and fatty acid derivatives, to the base asphalt binder to achieve the specified performance grade. Softeners shall be dissolved, dispersed, or reacted in the asphalt binder to enhance its performance and shall remain compatible with the asphalt binder with no separation. Softeners shall not be added to modified PG asphalt binder as defined in Articles 1032.05(b)(1) or 1032.05(b)(2).

An Attenuated Total Reflectance-Fourier Transform Infrared spectrum (ATR-FTIR) shall be collected for both the softening compound as well as the softener modified

asphalt binder at the dose intended for qualification. The ATR-FTIR spectra shall be collected on unaged softener modified binder, 20-hour Pressurized Aging Vessel (PAV) aged softener modified binder, and 40-hour PAV aged softener modified binder. The ATR-FTIR shall be collected in accordance with Illinois Test Procedure 601. The electronic files spectral files (in one of the following extensions or equivalent: *.SPA, *.SPG, *.IRD, *.IFG, *.CSV, *.SP, *.IRS, *.GAML, *.[0-9], *.IGM, *.ABS, *.DRT, *.SBM, *.RAS) shall be submitted to the Central Bureau of Materials.

Softener modified asphalt binders shall meet the requirements in Table 4.

Table 4 - Requirements for Softener Modified Asphalt Binders			
	Asphalt Grade		
	SM PG 46-28 SM PG 46-34		
Test	SM PG 52-28 SM PG 52-34		
	SM PG 58-22 SM PG 58-28		
	SM PG 64-22		
Small Strain Parameter (AASHTO PP 113)			
BBR, ΔTc, 40 hrs PAV (40 hrs	-5°C min.		
continuous or 2 PAV at 20 hrs)			
Large Strain Parameter (Illinois Modified			
AASHTO T 391) DSR/LAS Fatigue	> EA 0/		
Property, Δ G* peak τ, 40 hrs PAV	≥ 54 %		
(40 hrs continuous or 2 PAV at 20 hrs)			

The following grades may be specified as tack coats.

Asphalt Grade	Use
PG 58-22, PG 58-28, PG 64-22	Tack Coat"

Revise Article 1031.06(c)(1) and 1031.06(c)(2) of the Standard Specifications to read:

"(1) RAP/RAS. When RAP is used alone or RAP is used in conjunction with RAS, the percentage of virgin ABR shall not exceed the amounts listed in the following table.

HMA Mixtures - RAP/RAS Maximum ABR % ^{1/2/}						
Ndesign Binder Surface Polymer Modified Binder Surface Binder or Surface ^{3/}						
30	30	30 10				
50	25	15	10			
70	15	10	10			
90	10	10	10			

1/ For Low ESAL HMA shoulder and stabilized subbase, the RAP/RAS ABR shall not exceed 50 percent of the mixture.

- 2/ When RAP/RAS ABR exceeds 20 percent, the high and low virgin asphalt binder grades shall each be reduced by one grade (i.e. 25 percent ABR would require a virgin asphalt binder grade of PG 64-22 to be reduced to a PG 58-28).
- 3/ The maximum ABR percentages for ground tire rubber (GTR) modified mixes shall be equivalent to the percentages specified for SBS/SBR polymer modified mixes.
- (2) FRAP/RAS. When FRAP is used alone or FRAP is used in conjunction with RAS, the percentage of virgin asphalt binder replacement shall not exceed the amounts listed in the following table.

HMA Mixtures - FRAP/RAS Maximum ABR % ^{1/2/}						
Ndesign	Ndesign Binder Surface Polymer Modifi Binder or Surface					
30	55	45	15			
50	45	40	15			
70	45	35	15			
90	45	35	15			
SMA			25			
IL-4.75			35			

- 1/ For Low ESAL HMA shoulder and stabilized subbase, the FRAP/RAS ABR shall not exceed 50 percent of the mixture.
- 2/ When FRAP/RAS ABR exceeds 20 percent for all mixes, the high and low virgin asphalt binder grades shall each be reduced by one grade (i.e. 25 percent ABR would require a virgin asphalt binder grade of PG 64-22 to be reduced to a PG 58-28).
- 3/ The maximum ABR percentages for GTR modified mixes shall be equivalent to the percentages specified for SBS/SBR polymer modified mixes."

Add the following to the end of Note 2 of Article 1030.03 of the Standard Specifications.

"A dedicated storage tank for the ground tire rubber (GTR) modified asphalt binder shall be provided. This tank shall be capable of providing continuous mechanical mixing throughout and/or recirculation of the asphalt binder to provide a uniform mixture. The tank shall be heated and capable of maintaining the temperature of the asphalt binder at 300 °F to 350 °F (149 °C to 177 °C). The asphalt binder metering systems of dryer drum plants shall be calibrated with the actual GTR modified asphalt binder material with an accuracy of ± 0.40 percent."

SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)

Effective: November 2, 2017 Revised: April 1, 2019

Replace the second paragraph of Article 109.12 of the Standard Specifications with the following:

"This mobilization payment shall be made at least seven days prior to the subcontractor starting work. The amount paid shall be at the following percentage of the amount of the subcontract reported on form BC 260A submitted for the approval of the subcontractor's work.

Value of Subcontract Reported on Form BC 260A	Mobilization Percentage
Less than \$10,000	25%
\$10,000 to less than \$20,000	20%
\$20,000 to less than \$40,000	18%
\$40,000 to less than \$60,000	16%
\$60,000 to less than \$80,000	14%
\$80,000 to less than \$100,000	12%
\$100,000 to less than \$250,000	10%
\$250,000 to less than \$500,000	9%
\$500,000 to \$750,000	8%
Over \$750,000	7%"

VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE)

Effective: November 1, 2021 Revised: November 1, 2022

Add the following paragraph after the first paragraph of Article 701.08 of the Standard Specifications:

"The Contractor shall equip all vehicles and equipment with high-intensity oscillating, rotating, or flashing, amber or amber-and-white, warning lights which are visible from all directions. In accordance with 625 ILCS 5/12-215, the lights may only be in operation while the vehicle or equipment is engaged in construction operations."

WORKING DAYS (BDE)

Effective: January 1, 2002

The Contractor shall complete the work within 30 working days.

State of Illinois Department of Transportation Bureau of Local Roads and Streets

SPECIAL PROVISION FOR RAILROAD PROTECTIVE LIABILITY INSURANCE FOR LOCAL LETTINGS

Effective: March 1, 2005 Revised: January 1, 2006

All references to Sections or Articles in this specification shall be construed to mean a specific Section or Article of the Standard Specifications for Road and Bridge Construction, adopted by the Department of Transportation.

<u>Railroad Protective Liability Insurance</u>. The contractor will be required to carry Railroad Protective Liability and Property Damage Liability Insurance in accordance with Article 107.11 of the Standard Specifications. A separate policy is required for each railroad indicated on the attached form unless otherwise noted. The limits of liability for each policy are listed on the attached form. The minimum limits of liability shall be in accordance with Article 107.11 of the Standard Specifications.

Basis of Payment. The costs for providing insurance, as noted above, will be paid for at the contract unit price per Lump Sum for RAILROAD PROTECTIVE LIABILITY INSURANCE.

APPROVAL OF INSURANCE: The ORIGINAL and one CERTIFIED copy of each required policy shall be submitted for approval to the following address:

The contractor will be advised when approval of the insurance has been received from the railroad(s). Before any work begins on railroad right-of-way, the Contractor shall submit to the Resident Engineer evidence that the required railroad protective liability insurance has been approved by the railroad(s). The Contractor shall also provide the Resident Engineer with expiration date of each required policy.

RAILROAD PROTECTIVE LIABILITY INSURANCE FORM

NAMED INSURED & ADDRESS	NUMBER & SPEED OF PASSENGER TRAINS	NUMBER & SPEED OF FREIGHT TRAINS
DOT/AAR Number:	RR Mile Post:	
Liability Limits: Combined Single Limit	\$	Aggregate Limit <u></u> \$
For Freight/Passenger Information Cont	act:	Phone:
For Insurance Information Contact:		Phone:
DOT/AAR Number:	RR Mile Post:	
Liability Limits: Combined Single Limit	\$	Aggregate Limit_\$
For Freight/Passenger Information Cont	act:	Phone:
For Insurance Information Contact:		Phone:
DOT/AAR Number:	RR Mile Post:	
Liability Limits: Combined Single Limit		Aggregate Limit \$
For Freight/Passenger Information Cont		
For Insurance Information Contact:		Phone:
DOT/AAR Number:	RR Mile Post	
Liability Limits: Combined Single Limit		Aggregate Limit \$
For Freight/Passenger Information Cont		
For Insurance Information Contact:		Phone:

State of Illinois Department of Transportation Bureau of Local Roads and Streets

SPECIAL PROVISION FOR INSURANCE

Effective: February 1, 2007 Revised: August 1, 2007

All references to Sections or Articles in this specification shall be construed to mean specific Section or Article of the Standard Specifications for Road and Bridge Construction, adopted by the Department of Transportation.

The Contractor shall name the following entities as additional insured under the Contractor's general liability insurance policy in accordance with Article 107.27:

The entities listed above and their officers, employees, and agents shall be indemnified and held harmless in accordance with Article 107.26.

State of Illinois Department of Transportation Bureau of Local Roads and Streets

SPECIAL PROVISION FOR EQUIPMENT RENTAL RATES

Effective: January 1, 2012

All references to Sections or Articles in this specification shall be construed to mean a specific Section or Article of the Standard Specifications for Road and Bridge Construction, adopted by the Department of Transportation.

Replace Article 109.04(b)(4) with the following:

"(4) Equipment. For any machinery or special equipment (other than small tools) the use of which has been authorized by the Engineer, the Contractor will be paid according to the latest revision of "SCHEDULE OF AVERAGE ANNUAL EQUIPMENT OWNERSHIP EXPENSE" and latest index factor as issued by the Illinois Department of Transportation. The equipment should be of a type and size reasonably required to complete the extra work."

State of Illinois DEPARTMENT OF TRANSPORTATION Bureau of Local Roads & Streets SPECIAL PROVISION FOR LOCAL QUALITY ASSURANCE/ QUALITY MANAGEMENT QC/QA Effective: January 1, 2022

Replace the first five paragraphs of Article 1030.06 of the Standard Specifications with the following:

"**1030.06 Quality Management Program.** The Quality Management Program (QMP) will be Quality Control / Quality Assurance (QC/QA) according to the following."

Delete Article 1030.06(d)(1) of the Standard Specifications.

Revise Article 1030.09(g)(3) of the Standard Specifications to read:

"(3) If core testing is the density verification method, the Contractor shall provide personnel and equipment to collect density verification cores for the Engineer. Core locations will be determined by the Engineer following the document "Hot-Mix Asphalt QC/QA Procedure for Determining Random Density Locations" at density verification intervals defined in Article 1030.09(b). After the Engineer identifies a density verification location and prior to opening to traffic, the Contractor shall cut a 4 in. (100 mm) diameter core. With the approval of the Engineer, the cores may be cut at a later time."

Revise Article 1030.09(h)(2) of the Standard Specifications to read:

"(2) After final rolling and prior to paving subsequent lifts, the Engineer will identify the random density verification test locations. Cores or nuclear density gauge testing will be used for density verification. The method used for density verification will be as selected below.

	Density Verification Method
	Cores
X	Nuclear Density Gauge (Correlated when paving ≥ 3,000 tons per mixture)

Density verification test locations will be determined according to the document "Hot-Mix Asphalt QC/QA Procedure for Determining Random Density Locations". The density testing interval for paving wider than or equal to 3 ft (1 m) will be 0.5 miles (800 m) for lift thicknesses of 3 in. (75 mm) or less and 0.2 miles (320 m) for lift thicknesses greater than 3 in. (75 mm). The density testing interval for paving less than 3 ft (1 m) wide will be 1 mile (1,600 m). If a day's paving will be less than the prescribed density testing interval, the length of the day's paving will be the interval for that day. The density testing interval for mixtures used for patching will be 50 patches with a minimum of one test per mixture per project.

If core testing is the density verification method, the Engineer will witness the Contractor coring, and secure and take possession of all density samples at the

density verification locations. The Engineer will test the cores collected by the Contractor for density according to Illinois Modified AASHTO T 166 or AASHTO T 275.


If nuclear density gauge testing is the density verification method, the Engineer will conduct nuclear density gauge tests. The Engineer will follow the density testing procedure detailed in the document "Illinois Modified ASTM D 2950, Standard Test Method for Density of Bituminous Concrete In-Place by Nuclear Method".

A density verification test will be the result of a single core or the average of the nuclear density tests at one location. The results of each density test must be within acceptable limits. The Engineer will promptly notify the Contractor of observed deficiencies."

Revise the seventh paragraph and all subsequent paragraphs in Section D. of the document "Hot-Mix Asphalt QC/QA Initial Daily Plant and Random Samples" to read:

"Mixtures shall be sampled from the truck at the plant by the Contractor following the same procedure used to collect QC mixture samples (Section A). This process will be witnessed by the Engineer who will take custody of the verification sample. Each sample bag with a verification mixture sample will be secured by the Engineer using a locking ID tag. Sample boxes containing the verification mixture sample will be sealed/taped by the Engineer using a security ID label."

TAZEWELL COUNTY 23-00018-06-RS



TAZEWELL COUNTY Sec. 23-00018-06-RS

SUMMARY OF QUANTITIES


PAY ITEM	UNIT	QUANTITY
POLYMERIZED BITUMINOUS MATERIALS (TACK COAT)	POUND	145,841
HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,800
TEMPORARY RAMP	SQ YD	140
HOT-MIX ASPHALT BINDER COURSE, IL 9.5FG, N50	TON	6,942
POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N50	TON	8,331
MATERIAL TRANSFER DEVICE	TON	8,331
INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	353
HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	98,296
AGGREGATE SHOULDERS, TYPE B (SPECIAL)	TON	1,534
SHORT TERM PAVEMENT MARKING	FOOT	19,952
SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	1,663
RAISED REFLECTIVE PAVEMENT MARKER	EACH	347
RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	347
CLASS D PATCH, TYPE IV, 6 INCH	SQ YD	1182
RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1
TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
MOBILIZATION	L SUM	1

Page 1 of 2 Washington Rd. (CH 3) - City of Washington (Sta. 2+65) Southerly to US 150 (Sta. 281+70)

Road Length: Bridge Omission: Net Length: Road Width: Hot-Mix Asphalt Shoulder Width: Aggregate Shoulder Width:			27,683 22 5	Feet
HMA Binder Course thickness: P HMA Surface Course thickness:				inches Inches
Bituminous Area:	Roadway, Shoulders, and Turnlane Sideroads, Drives, Etc.:	s: total	99,178 2,100 101,278	SY
POLYMERIZED BITUMINOUS MAT 0.08 lb/SF on Milled Sur	ERIALS (TACK COAT): face 0.08 lb/SF between lifts		145,841	POUND
HOT-MIX ASPHALT SURFACE REI Ends, Sideroads, & Entr			1,800	SY
TEMPORARY RAMPS:			140	SY
HOT-MIX ASPHALT BINDER COUP Roadway & Shoulders	RSE, IL 9.5FG, N50:		6,942	TON
POLYMERIZED HOT-MIX ASPHAL Roadway & Shoulders	T SURFACE COURSE, IL 9.5, MIX "I	D", N50:	8,331	TON
MATERIAL TRANSFER DEVICE: HMA Surface Course			8,331	TON
INCIDENTAL HOT-MIX ASPHALT S Sideroads, Entrances, e			353	TON
HOT-MIX ASPHALT SURFACE REI	MOVAL, 1 1/2":		98,296	SY
AGGREGATE SHOULDERS, TYPE Roadway: Radius', Drives, etc.:	B (SPECIAL): 1414 TONS 120 TONS Total 1534 TONS		1,534	TON
SHORT-TERM PAVEMENT MARKI	NG: Lifts 4' / 40' = 11088 foot			
	$\frac{11088 1001}{4' / 100' \times 2} = \frac{8864 \text{ foot}}{19952 \text{ foot}}$	-	19,952	FOOT
SHORT TERM PAVEMENT MARKI	NG REMOVAL:		1,663	SQ FT

				TAZEWELL COUNTY Sec. 23-00018-06-RS		
Page 2 of 2 Washington Rd. (CH 3) - City of Washington (Sta. 2+65) Southerly to US 150 (Sta. 281+70)						
RAISED REFLECTIVE PAVEMENT M 1 marker / 80'	ARKER:			347 EACH		
RAISED REFLECTIVE PAVEMENT M	ARKERS R	EMOVAL:		347 EACH		
CLASS D PATCH, TYPE IV, 6 INCH:				1,182 SY		
5' HMA Shoulders	Length	Width				
	Feet	Feet	SY			
Sta. 130+15 to 132+15 RT	200	5	111 SY			
Sta. 149+40 to 151+20 RT	180	5	100 SY			
Sta. 152+90 to 154+60 RT	170	5	94 SY			
Sta. 189+10 to 190+90 LT	180	5	100 SY			
Sta. 205+10 to 208+10 LT	300	5	167 SY			
Sta. 213+50 to 215+30 RT	180	5	100 SY			
Sta. 229+50 to 231+20 LT	170	5	94 SY			
Sta. 233+60 to 240+70 LT	710	5	394 SY			
Sta. 245+20 to 245+60 RT	40	5	22 SY			
		Total	1182 SY			
RAILROAD PROTECTIVE LIABILITY	INSURANC	E:		1 L SUM		
TRAFFIC CONTROL AND PROTECTI	ON, (SPEC	IAL):		1 L SUM		
MOBILIZATION:				1 L SUM		

TYPICAL CROSS SECTION C.H. 3 - WASHINGTON ROAD




NOTE: *EXISTING 5' HOT-MIX ASPHALT SHOULDER SHALL BE PATCHED WITH CLASS D PATCHES, TYPE IV, 6" AT LOCATIONS SHOWN ON THE QUANTITY SHEET.

LOCATION: WASHINGTON RD. (CH 3)								
MIXTURE USE:	CLASS D PATCHES	CLASS D PATCHES	BINDER	SURFACE				
	(TOP LIFT)	(BOTTOM LIFT)						
PG:	PG 64-22	PG 64-22	PG 58-28	SBS 70-22				
DESIGN AIR VOIDS:	4% @ Ndes 50	4% @ Ndes 50	4% @ Ndes 50	4% @ Ndes 50				
MIXTURE COMPOSTION:	IL 9.5	IL 19.0	IL 9.5FG	IL 9.5				
(MIXTURE GRADATION)								
FRICTION AGGREGATE:	MIXTURE D	NONE	NONE	MIXTURE D				

Section: 23-00018-06-RS Route: CH 3 - WASHINGTON RD. Location: City of Washington (Sta. 2+65) southerly to US 150 (Sta. 281+70)


TAZEWELL COUNTY SEC. 23-00018-06-RS

STANDARD FOR HOT-MIX ASPHALT SURFACING AT SIDEROADS, ENTRANCES AND MAILBOXES



Notes: 1. Dimensions are approximate and may be adjusted in the field by the Engineer


- 2. The cost of preparing driveways will be considered included in the type of surface being constructed and will not be measured separately for payment. (See Spec. Prov.)
- 3. Place AGGREGATE SHOULDERS, TYPE B (SPECIAL) behind drives to blend into existing aggregate drives.



CASE 1 : WITH HOT MIX ASPHALT SURFACE REMOVAL (COLD MILLING)

	I	AFER RAIES		
SPECIAL NOTE	ELEMENT	MAINLINE INTERSTATES &	ALL	1
NUMBER		4-LANE EXPRESSWAYS	OTHERS	
	BUTT JOINT	1:480	1:240	2
	TAPER RATE			
2	TEMPORARY RAMP	1:80	1:40	
	TAPER RATE			3

TABLE A TAPER RATES



CASE 2 : NO HOT MIX ASPHALT SURFACE REMOVAL (COLD MILLING)

01-01-97	RENUM. C-23.01, NEW REVISION BOX	T.P.	08-21-13	MAJOR MODIFICATIONS	R.D.		
04-01-97	CORRECTION TO DEPTH	J.A.	04-12-16	MINOR CORRECTIONS	R.D.	STATE OF ILLINOIS	BUTT JOINTS
09-15-05	REVISED DESIGNER NOTE	M.M.A.	02-14-17	ADDED NOTE 5	R.D.	DEPARTMENT OF TRANSPORTATION	
10-16-06	REVISED TO 2007 SPEC.	M.A.	07-16-19	Wording and Spelling corrections	R.D.	Page 36	NOT TO SCALE

GENERAL NOTES

1. The work shall be done in accordance with Article 406.08 and the Special Provision for Butt Joints.

2. The pavement surface to be removed may be either bituminous or P.C. concrete. The work shall be performed in accordance with Article 440.04 and the Special Provisions for Butt Joints.


3. The saw cut joints shall be primed just prior to the placing of bituminous material. The work will be in accordance with the applicable portions of Article 406.05.

4. The length of butt joint is based on the taper rate times change in cold milling depth within the butt joint pay limits, unless otherwise indicated.


5. Temporary ramps are paid for separately and not included in the cost of the butt joints.

All dimensions are in inches (millimeters) unless otherwise noted.

	F.A. RTE.	SEC	TION		COUNTY	TOTAL SHEETS	SHEET NO.
TS							
SHT. 1 OF 3					CONTRACT	NO.	
CADD STD. 406101-D4	FED. RO	DAD DIST. NO.	ILLINOIS FEE). Al	D PROJECT		




CASE 3 : HOT MIX ASPHALT SURFACE REMOVAL (COLD MILLING) TIE-IN TO EXISTING BITUMINOUS TAPER



			F.A. SECTION	COUNTY TOTAL SHEE
	STATE OF ILLINOIS	BUTT JOINTS	RIE.	SHEETS NU.
	DEPARTMENT OF TRANSPORTATION		SHT. 2 OF 3	CONTRACT NO.
	Page 37	NOT TO SCALE	CADD STD. 406101-D4 FED. ROAD DIST. NO. ILLINOIS	FED. AID PROJECT


All dimensions are in inches (millimeters) unless otherwise noted.



Prop. Hot Mix Asphalt surf. removal (cold milling) per plans.


All dimensions are in inches (millimeters) unless otherwise noted.

			F.A. RTE.		SEC	TION	COUNTY	TOTAL SHEETS	SHEET NO.
NTS									
	C 4 D D	SHT. 3 OF 3					CONTRACT	NO.	
	CADD	STD. 406101-D4	FED. RO	DAD DIST. N	10.	ILLINOIS FED. A	ID PROJECT		




IONS	
sign	
with	
RKERS'	

OFF-RD OPERATIONS, 2L, 2W, 15' (4.5 m) TO 24" (600 mm) **FROM PAVEMENT EDGE**




SIONS	
sign	OFF-RD MOVING OPERATIONS,
with	2L, 2W, DAY ONLY
	ZL, ZW, DAT UNLT
RKERS'	
	STANDARD 701011-04




Page 41


IONS
acing in taper.
gn.




LANE CLOSURE, 2L, 2W, **SHORT TIME OPERATIONS**

STANDARD 701301-04






SIONS
ign.
n 's



SIONS
ge and
" (900 m) height.
rk zone
from
background.







G20-I104(0)-6036

G20-I105(0)-6024


This signing is required for all projects 2 miles (3200 m) or more in length.

ROAD CONSTRUCTION NEXT X MILES sign shall be placed 500' (150 m) in advance of project limits.

END CONSTRUCTION sign shall be erected at the end of the job unless another job is within 2 miles (3200 m).

Dual sign displays shall be utilized on multilane highways.

WORK LIMIT SIGNING



Sign assembly as shown on Standards or as allowed by District Operations.



G20-I103-6036

This sign shall be used when the above sign assembly is used.


HIGHWAY CONSTRUCTION SPEED ZONE SIGNS


**** R10-I108p shall only be used along roadways under the juristiction of the State.

TRAFFIC CONTROL DEVICES

(Sheet 2 of 3)


STANDARD 701901-08






Reduce to 40' (12.2 m) o.c. on curves with posted or advisory speeds of 45 mph (70 km/h) or less.


TWO-LANE / TWO-WAY





*,** See MULTI LANE DIVIDED detail for lane marker notes.


MULTI-LANE UNDIVIDED




 * $\,$ Reduce to 40' (12.2 m) o.c. on curves where advisory speeds are 10 mph (15 km/h) lower than posted speeds.


W4-2

** Where double lane line markers are specified, they shall be spaced as shown.



MULTI-LANE DIVIDED





*,** See MULTI LANE DIVIDED detail for lane marker notes.

TWO-WAY LEFT TURN